

SUGGESTED SEQUENCE OF INSPECTIONS

SWPPP

Initial SWPPP at Plan Review
Monthly SWPPP inspection until project is complete

ROUGH PLUMB

Setbacks
Soil pipe in or under slab
*Construction loop

Forms Survey (added on 8/1/2011)

FOUNDATION

Excavation-Forms-Reinforcing
Copper pipe in or under slab
Under slab electric

FRAME

Lead Test
*Brick lug / Lath
Top Out Plumbing
Rough HVAC
Gas Service
*Waterline
*Sewer Line
Rough Electric
Framing
Poly Seal
Wind bracing-Straps/Panels

INSULATION

FINISH WIRING INSPECTION

FINALS

Plumbing
Heating
Electrical
*Driveways-Sidewalks, Etc.
Building

*** INDICATES THAT INSPECTION CAN BE ACCOMPLISHED ANYTIME
BEFORE THE FINAL IS CALLED FOR**

**CHARLES R. PADGETT, JR.
BUILDING OFFICIAL**